

数量総括書

海野線

P-1

道路土工

舗装版切断	7.5 * 2.0	=	15.0 m
舗装版破碎	359.5	=	359.5 m ²
As運搬 L=6.8km	359.5 * 0.04	=	14.4 m ³
As処分	14.4 * 2.35	=	33.8 t
掘削	60.6 * 0.30	=	18.2 m ³
土砂運搬 L=2.5km	60.6 * 0.30	=	18.2 m ³

舗装工

不陸整正 C-25 t=3cm	298.9	=	298.9 m ²
不陸整正 補足材なし	60.6	=	60.6 m ²
下層路盤 RC-40 t=20cm	60.6	=	60.6 m ²
上層路盤 M-25 t=10cm	60.6	=	60.6 m ²
表層工 再密13F t=4cm	359.5	=	359.5 m ²

任意仮設工

交通誘導員B	4.0	=	4.0 人
--------	-----	---	-------

舗装面積計算書

測点or ポイント	点間	取壊し4cm			舗装4cm (再密13F)		
		幅員	平均	面積	幅員	平均	面積
	-						
0.0	-	10.80			10.80		
4.0	4.0	8.00	9.40	37.60	8.00	9.40	37.60
7.0	3.0	7.30	7.65	22.95	7.30	7.65	22.95
10.0	3.0	7.30	7.30	21.90	7.30	7.30	21.90
20.0	10.0	7.00	7.15	71.50	7.00	7.15	71.50
30.0	10.0	6.80	6.90	69.00	6.80	6.90	69.00
40.0	10.0	6.40	6.60	66.00	6.40	6.60	66.00
50.0	10.0	7.70	7.05	70.50	7.70	7.05	70.50
小計	50.0			359.5			359.5