

計 算 調 書 (加沢区工事)				
工種／種別		単位	総量	摘 要
【社会資本整備総合交付金事業】				
道路土工				
掘削		m ³	6.6	
埋め戻し		m ³	2.3	
DT運搬	DT2t 6.6-2.3	m ³	4.3	
取壊し工				
構造物取壊し	(0.2+0.32)/2*9.8	m ³	2.5	
Con殻積込		m ³	2.5	
Con殻運搬		m ³	2.5	
Con処分	2.5×2.35	t	5.9	
小型構造物工				
重力式擁壁	(0.17+0.29)/2*9.8	m ³	2.3	
舗装工				
下層路盤工	RC-40 t=20cm	m ²	7.9	
上層路盤工	M-25 t=10cm	m ²	7.9	
表層工	t=4cm 再生密粒度As13F	m ²	7.8	
道路附属施設工				
境界杭設置工		本	1	
境界鋳設置工		枚	1	
【長期計画土木事業】				
取壊し工				
舗装版切断	2.6+10.0+3.9+3.9	m	20.4	
舗装版取壊し		m ²	95.3	
As殻運搬		m ³	3.8	
As処分	3.8×2.35	t	9.0	
舗装工				
不陸整正	補足材あり M-25 平均t=3cm	m ²	95.3	
表層工	t=4cm 再生密粒度As13F	m ²	95.3	

[illegible]

当初土坪計算書

測点	断面			平均断面			距離	体積		
	掘削	埋戻(発生土)	埋戻(RC-40)	掘削	埋戻(発生土)	埋戻(RC-40)		掘削	埋戻(発生土)	埋戻(RC-40)
0.0	0.21	0.00	0.00							
3.0	0.21	0.00	0.00	0.21	0.00	0.00	3.0	0.6	0.0	0.0
3.0	0.46	0.15	0.00	0.34	0.08	0.00				
12.8	0.75	0.30	0.00	0.61	0.23	0.00	9.8	6.0	2.3	0.0
小計							12.8	6.6	2.3	0.0